BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work : Supply and Instalation of CCTV Camaras at Selected Points with annual Maintenance in Ward No. 11, Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	4.00	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos	61592.00	Rupees Sixty One Thousand Five Hundred Ninety Two Only
2	12.00	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos	3349.00	Rupees Three Thousand Three Hundred Forty Nine Only
3	12.00	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos	16610.00	Rupees Sixteen Thousand Six Hundred Ten Only
4	12.00	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos	1212.00	Rupees One Thousand Two Hundred Twelve Only
5	10.00	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos	11979.00	Rupees Eleven Thousand Nine Hundred Seventy Nine Only
6	14.00	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos	1170.00	Rupees One Thousand One Hundred Seventy Only
7	3.00	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional	Nos	52580.00	Rupees Fifty Two Thousand Five Hundred Eighty Only
8	3.00	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos	202074.00	Rupees Two Lakh(s) Two Thousand Seventy Four Only
9	5.00	4 TB SATA for storage and fitted in the NVR Device for storage	Nos	17937.00	Rupees Seventeen Thousand Nine Hundred Thirty Seven Only
10	18.00	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos	1197.00	Rupees One Thousand One Hundred Ninety Seven Only
11	18.00	Power supply for the camera.	Nos	361.00	Rupees Three Hundred Sixty One Only
12	18.00	Ethernet Switch for connectivity to Internet and Camera	Nos	745.00	Rupees Seven Hundred Forty Five Only

Signature of the Contractor

Executive Engineer

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
13	20.00	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos	305.00	Rupees Three Hundred Five Only
14	18.00	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos	15700.00	Rupees Fifteen Thousand Seven Hundred Only
15	16.00	Installation, Erection & commissioning charges	Nos	3972.00	Rupees Three Thousand Nine Hundred Seventy Two Only
		EIRL			
E1	6.00	Providing CCTV MS Poles with camera fixing brackets 5 to 6Mtrs hight box inclusive of all taxes transortation charges as per the direction of engineer incharge.	Nos	18447.50	Rupees Eighteen Thousand Four Hundred Forty Seven And Paise Fifty Only

K. Sankar Reddy
Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92